From: SMTP%"sshears@lodestar.gb.nrao.edu" 18-NOV-1991 15:48 To: backer@bkypsr.berkeley.edu, bania@buast4.bu.edu, Subj: Preliminary Design Considerations

Date: Mon, 18 Nov 91 15:40:05 EST From: (SUE SHEARS) sshears@lodestar.gb.nrao.edu Message-Id: <9111182040.AA05136@arcturus> To: backer@bkypsr.berkeley.edu, bania@buast4.bu.edu,

Message-Id: <9111182040.AA05136@arcturus> To: backer@bkypsr.berkeley.edu, bania@buast4.bu.edu, demerson@tucvax.tuc.nrao.edu, dtw@pupgg.princeton.edu, gseielst@cvax.cv.nrao.edu, haynes@astrosun.tn.cornell.edu, heiles@bkyast.span, hugh@astro.lsa.umich.edu, jlockman@cvax.cv.nrao.edu, john@astl.spa.umn.edu, loris@naic.edu, mdavis@naic.edu, moran@cfa.harvard.edu, nzs@radio.caltech.edu., pnapier@zia.aoc.nrao.edu, psolomon@sbccmail.bitnet, riccardo@astrosun.tn.cornell.edu, rmaddale@lodestar.GB.NRAO.EDU, schloerb@fcraol.phasts.umass.edu, snyder@prairie.astro.uiuc.edu, srk@deimos.caltech.edu, sshears@arcturus.GB.NRAO.EDU Subject: Preliminary Design Considerations

National Radio Astronomy Observatory Joint Operations Center Green Bank, West Virginia

PRELIMINARY DESIGN CONSIDERATIONS

Center will have many uses; truly a Joint Operations Center for control and administration of many projects. Goal is to integrate USNO activities in with NSF and other activities in a way that minimizes cost and maximizes efficiency. The various parts of the Center are not divided by project or its funding agency. Nor can people or equipment be precisely separated into projects.

Memorandum of Understanding, NRAO-USNO

Funding Agencies Involved

Astronomy Division Education Division

USNO NASA

Code O--Operations of Satellite Tracking Stations Code S--Science Life Sciences

demerson@tucvax

Activities_

GBT Earth-Space Communications Station for OVLBI Astrometric VLBI Antenna Alternate Master Clocks 140 ft Telescope (eventually for SETI)

Location of Center

ુ અન

Unified with Jansky Laboratory via an Entrance/Reception/Visitor Center between the new building and the existing one.

Oriented such that telescopes can be seen from Control Room Therefore, large windowed wall facing approximately West. Necessitates at least a second story

List of Basic Requirements for Center

General

.

Compatibility with local environment and with existing buildings

Design to reflect purpose of NRAO: radio astronomy and radio telescopes

Possibility for expansion

Interior walls between offices capable of movement and removal

Views from within able to capture natural beauty of surroundings

Physical Requirements Energy Efficient (Average Annual Heating Degree Days = 6500)

Air Conditioned

Rest rooms for both sexes on all above-ground floors Provision for Handicapped Shower in each sexUs restroom on ground floor

Entrance ramp for Handicapped

Elevator With indoor and outdoor access from loading dock--roof over dock Safe for use by people as well as equipment Standard elevator

Maximum weight capacity 1,000-2,000 lbs. Door opening approx. >7 ft wide and >6'8" high

Closets for janitorial supplies Sink

Shelves

Rooms

Control Room for GBT

Equipment Room for GBT, adjacent but separated from Control Room

Common Control Area for USNO, SETI, OVLBI Adjacent to GBT Control Room Both easy back and forth travel between rooms, but some barrier offering each the chance to concentrate without disturbance from the other.

Equipment Room for USNO, SETI, OVLBI Operations Adjacent to GBTUS Equipment Room but with some specifically assigned space for various functions. Some apparatus is common to >1 project. These need to be co-located.

Area for Computing Facilities for all activities (NSF, USNO, NASA) In very close contact to Control Room, telescope

operator, and equipment room Location where astronomer, who is the central focus the Observatory exists for, commands telescope, analyzes data, and monitors functioning of equipment. Lighting must not glare off computer screens A common location for peripherals: tape drives, CD ROMplayers, printers, plotters, etc. Carrels (not completely enclosed) for several workstations

Control Rooms located so that they are easy to get to, but not on a path between two active centers. (No shortcutting through Control areas en route between other locations.) Placing Control Rooms along west wall helps satisfy this requirement.

Control Rooms, Equipment Rooms, and Computing Area could be on contiguous computer floor, so that partitions could be moved freely to readjust space.

Office for Site Director; adjoining office for Secretary

Office for Telescope Operators, just off Control Rooms

Storage Room near Control Rooms, for Magnetic Tapes Disks Computer paper Supplies File cabinets Copy Machine Facsimile Machine

Approx. 17 offices for resident scientists, programmers, and engineers. Mix of personnel for all projects, NSF, USNO (Clocks and Antennas), NASA (SETI and OVLBI), Other

Two offices for telescope users

Two offices for Visiting Scientists (double occupancy)

One office for the Head of Telescope Operations

One office for Telescope Supervisor (Head Operator)

One office for Head of USNO Activities

Area for workbenches, spare parts, tools, and test equipment (oscilloscopes spectrum analyzers, signal generators, and the like)

Near Equipment Rooms Near an EngineerUs Office

Indoor Antenna Range and Screen Room Walls, floor, and ceiling screened against leakage of microwaves Interior covered with absorber to kill microwave

reflections Possibly windowless room (in basement?) Conference Room

Auditorium/Lecture Hall

Special, isolated room for Atomic Clocks No through traffic Secure Enclosed Environmental Vaults

Utilities Room

Heat/Air Condition Entry for cables, optical fibers, telephone wires Electrical junction boxes

Kitchen/Canteen

Sink Refrigerator Hotplate Vending Machines

Special Requirements Equipment Rooms, Computing Rooms, and Indoor Antenna Test Range screened against microwave leakage (rfi protection)

Especially noisy devices need to be isolated and accorded sound baffling (limit sound level to <50 dbA in all areas)

Control Rooms, Equipment Rooms, Computing Area need computer floor

Forced air, temperature regulated, needs to be circulated through electronics racks with a minimum of noise.

Regulated electrical power for sensitive equipment (clocks, computers, electronics devices, etc.)

Diesel generator for backup power to atomic clocks

Emergency backup lights in all critical areas (in case of power failure)

Fire Detector Alarms throughout building

Fire Extinguishing Devices in Equipment Rooms and Computing Area

Distribution systems for Telephone

Computer connections to Networks

Hallways and entrances capable of supporting equipment rolled from Jansky Lab and from elevator/loading dock (i.e., "rollabe" floor and entrances wide and high enough).

Estimates of Square Feet Needed for Various Requirements

GBT Control Room

2,500 sq. ft.

GBT Equipment Room

2,000

| Common Control Area for USNO, SETI, OVI | LBT | 1,500 |
|---|------------------------|-----------------------|
| Equipment Room for USNO, SETI, and OVLBI devices | | 1,500 |
| Area for Computing Facilities | | 2,000 |
| Office for Site Director | | 330 |
| | | |
| Office for Secretary | | 170 |
| Office for Telescope Operators | | 300 |
| Storage Room | | 200 |
| Offices for resident professionals (single occupancy) (double occupancy) | 9 x 160 = 8 x 200 = | 1,440 1,600 |
| Offices for Telescope Users | 2 x 300 = | 600 |
| Offices for Visiting Scientists 2 x 300 |) = | 600 |
| Office for Head of Telescope Operations | S | 170 |
| Office for Telescope Supervisor | | 170 |
| Office for Head of USNO Activities | | 170 |
| Area for Workbenches | | 380 |
| Indoor Antenna Range and Screen Room | | 400 |
| Conference Room | | 400 |
| Auditorium | | 2,000 |
| Atomic Clock Rooms | ?2 x 3,000= | 6,000? |
| Office for Security Guards | | 120 |
| Utilities Room | | 300 |
| Kitchen/Canteen | | 200 |
| TOTAL | | 25,050 sq. ft. |
| (excluding enclosed connection to Jansky Lab and basic infrastructure requirements) | | |
| Connections to Various Places around Site Optical fibers to (at least) GBT | | |
| OVLBI Antenna 140 ft Telescope Astrometric VLBI Antenna Tour Center/Shops | | |
| Fiber system for distributing time and frequency references to all | | |

Fiber system for distributing time and frequency references to all antennas from Master Clock Room.

~

Audio and Visual cabling of antennas to Operations Center

Computer Connection to Internet

پر

Schedule for Completion Move into new Control Building should be completed by the end of 1993.