

NRAO Collaborations and Support to NASA

Three categories:

Use of NRAO infrastructure as part of a NASA or NASA-related space science project
Supplying ground station as part of space VLBI – VSOP/HALCA Use of NRAO
computing capabilities (VLBA correlator) for VSOP Production of advanced receivers,
etc Station electronics/observing system/data decoding electronics for VSOP at multiple
sites

Spacecraft Tracking and Telemetry from Green Bank P. R. Jewell 19 January 2005

1. Past projects

1.1 VSOP/HALCA.

NRAO Green Bank Operations very successfully participated in an orbiting VLBI project for five years (terminating in early 2002). The station electronics and observing system were designed and built by NRAO staff. The station was originally envisioned for the Russian-led Radioastron project, but was adapted for use by the Japanese-led VSOP/HALCA project (NASA Co-I). The station utilized the 45-Foot (14-m) telescope at Green Bank. A maser time/frequency tone was uplinked to the satellite and VLBI data were downlinked. NRAO built data decoding electronics that were subsequently replicated for use at a Russian station. The NRAO 45 Foot Earth Station had the best success rate for tracking passes for VSOP of any of the earth stations used for this project around the globe (>94% of all possible data recorded successfully). NASA was extremely pleased with the operation of the NRAO station in Green Bank, to the best of our knowledge. NRAO thus established an excellent reputation of efficient, cost-effective contract operations with this project. Our NASA contract managers for this project were James Costrell and Charles Holmes.

The contract with NASA for the Green Bank Earth Station was ~\$900k/yr in the latter years of operation. VLBA correlator operations in Socorro for VSOP/HALCA data were handled separately and were described in Jim Ulvestad's text.

1.2 Huygen's Probe

Described by Jim. The GBT made the first signal acquisition of the probe and thus confirmed that it was alive and functioning following entry into the Titan atmosphere. The GBT was used to track the Doppler data from the probe's carrier signal in total power mode as well as participating in the VLBI network. The combination of the VLBI positional data and the Doppler data will give the 3-D trajectory through the atmosphere. As noted by Jim, this will be the only Doppler wind data available.

2. Future Possibilities

2.1 Small-Diameter Earth Stations

The 45 Foot Telescope used for VSOP is presently being used for the Solar Radio Burst Spectrometer project, funded by an NSF grant (PI - Bastian). However, NRAO Green Bank also has a modern 20 meter antenna presently available that could be used for spacecraft tracking or other contract projects. This antenna was built in 1994 for the U.S. Naval Observatory for an earth orientation VLBI operation that terminated a few years ago. The antenna was transferred to the NSF at the conclusion of that contract and is available for NRAO operations or for contracts to be administered by NRAO.

2.2 140 Foot

The 140 Foot (43 Meter) telescope is potentially available for NASA contract operations within a few years. We are presently negotiating an outfitting and operations contract with MIT Lincoln Laboratory for use of the 140 Foot for low earth orbit satellite tracking. The tentative arrangement with Lincoln Lab calls for outfitting and modification to occur during FY05, and operations to follow during FY06 and FY07. The 140 Foot will be substantially modified for this task and will include a new control system and remote monitoring system. Lincoln Lab presently plans to use the 140 Foot for only 20-30 hours per week during the operations phase, so it is conceivable that other operational tasks could be multiplexed during the FY06-07 period, and certainly afterward. Since the Lincoln Lab project will cover the modernization costs, subsequent operations costs will be very reasonable.

It should be noted that while NRAO-GB did accommodate a low-power uplink for the VSOP/HALCA project, high-power uplinks are generally problematic for RFI reasons. In past discussions with NASA, telemetry downlink only operations were still attractive to them, as the downlink is the most time-intensive operation and command uplinks can be handled elsewhere within the DSN.

NASA has inquired in the past about using the 140 Foot for telemetry downlink, most recently for use with SOHO in the fall of 2003. We declined that offer because the very short timescale required and the associated impact on other operations at the time made the project infeasible for us. Past contact on such project possibilities has been through Barry Geldzahler and Charles Holmes.

2.3 The GBT

Although we should not offer the GBT for routine spacecraft tracking, the Huygens Probe experiment illustrates the unique capabilities of the GBT for special purpose, high-profile experiments or for tracking in emergency situations such as failure of a craft's high-gain antenna or failure of other DSN ground stations at critical times. The GBT is, of course, one of the highest sensitivity facilities on Earth. Signals from all Green Bank antennas including the GBT, 140 Foot, 20 Meter, 45 Foot, etc., can be brought back to the central Jansky Lab control room via fiber cable. It is a relatively straightforward operation to

ID	WBS	Task Name	2000		2001		2002		2003		2004		2005		2006	
			H1	H2	H1	H2	H1	H2	H1	H2	H1	H2	H1	H2	H1	H2
1	1.7.1	Central computing services														
2	1.7.1.1	Observatory wide computing														
3	1.7.1.2	Observatory computing security														
4	1.7.1.3	Observatory communications														
5	1.7.1.4	Observatory information infrastructure														
6	1.7.1.5	HQ Computing support														
7	1.7.2	Technology development														
8	1.7.2.1	AIPS++														
17	1.7.2.2	AIPS														
18	1.7.2.3	III-NCSA														
19	1.7.2.4	NSF/CISE Visualization														
20	1.7.2.5	Technology infrastructure														
21	1.7.3	Telescope computing														
22	1.7.3.1	Coordination and oversight														
23	1.7.3.2	VLA Control and Monitor management														
24	1.7.4	Data Management Initiative														
25	1.7.4.1	Establish and document processes														
26	1.7.4.2	Establish overall architecture														
27	1.7.4.3	Data dictionary construction														
28	1.7.4.4	Proposal handling														
41	1.7.4.5	Pipelines														
62	1.7.4.6	Archive														
80	1.7.4.7	Scheduling tool														
97	1.7.4.8	Dynamic scheduling														
113	1.7.5	COBRA proposal														
114	1.7.5.1	Develop and submit full proposal														
115	1.7.5.2	COBRA funding starts														

Project: dm
Date: Sun 2/18/01

Task

Split

Progress

Milestone

Summary

Project Summary

External Tasks

External Milestone

Deadline

4/2

9/3





